BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division
Schedule-B

NAME OF THE WORK: Potholes filling in main and cross roads of Bagalagunte in ward no. 14 in dasarahalli sub division

Sl. No	Description of work	Unit	Qty	Sanctioned Rate	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	KSRRB 300 - Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3 (P.142/I.19.1 PW, P & IWTD -SR 2016-17)	Cum	293.89	86.92	Rupees Eighty Six and Ninety Two Paise Only
2	Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. Specification No. 406 with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.(PWD SR 2016-17, P.No.158 I No.20.18)	Cum	244.90	1768.08	Rupees One Thousand Seven Hundred Sixty Eight and Eight Paise Only
3	Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3, back filling the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications - Filling pot holes and patch repairs with bituminous concrete, 40mm .(PWD SR 2016-17, P.No.257, I No. 35.5)	Sqm	979.65	302.10	Rupees Three Hundred Two and Ten Paise Only

Signature of the Contractor

Executive Engineer

4	Conveying the excavated earth silt, debris and over burden earth etc., to lead of 0 to 4 kms distance by using private vehicle this includes the cost of loading and unloading charges etc., complete (PWD SR 2016-17, P. 141 and 147 / Item No. 17.1 and 17.4)	Cum	293.89	72.80	Rupees Seventy Two and Eighty Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engineer